



Santa Barbara Remote Sensing

# MODIS Science Team Meeting PFM/FM1 Status

NASA GSFC Contract No. NAS 5-30800

5 May 1999

Raytheon



## **Agenda**



- PFM status/issues
- FM1 general status
- **FM1 emissive band accuracy results**
- Summary/Issues
- Appendix Out-of-Band spectral data



### **PFM Status/Issues**



- S/C at Vandenberg
- MODIS IGSE up and running
- Preparations underway for CPT and final tests
- S/C level science checks for MODIS have completed
- S/C->TDRSS->EDOS->DAAC level science checks not completed for MODIS by Raytheon/SBRS
  - Inability to access DAAC level science data prior to launch is a concern
  - Meeting scheduled this week with MCST



## FM1 Instrument Diagnostics/ Re-Work Completed



- November TV test uncovered anomalies
  - Low-current power supply shutdown
  - Noise on the redundant side
- Significant diagnostics have identified/solved these problems
- TV re-test is scheduled for mid-May
  - —TV test emphasis is on verifying fixes
  - —TV timeline is in the review cycle
- Instrument completion scheduled for mid-summer '99



# FM1 Power Supply Diagnostics/Rework Completed



- Power supply shut down under certain minimal load conditions during TV test
  - —All shutdowns related to instrument timing re-synchronization
- Three attempts at corrective action made within the supply
  - —Noise filtering
  - Pulse edge suppression during re-synchronization
  - Shield configuration changes
- Shutdown traced to oscillating circuit (within the supply)
  - Shield capacitance path caused the noise/oscillation
  - Bench test of re-worked supply demonstrated 50% margin to peak load, 90% margin to average science load
  - Instrument level test passed highest expected load (~10% margin to peak, ~40% margin to average)



# FM1 Rdt Diagnostics/Rework Completed



- High noise was observed during redundant mode testing
  - Noise appeared on both CFPA temperature telemetry and on the CFPA bands 5,6,7, and 20 thru 36
- Systematic disassembly/diagnostics isolated the primary cause to a wiring error
  - Main Electronics Module removed from instrument mainframe
  - Capacitor filtering/wire re-routing proved ineffective
  - Spectrum analyzer loop test performed on backplane in vicinity of problem
  - Two single-ended shields were found tied to clock lines instead of ground; high speed clocks were driving the shields
  - Shield drain wires were correctly terminated to ground
- Telemetry and CFPA noise are significantly reduced after repair; TV test will produce final noise results



# SDSM Sun Screen Diagnostics/Rework Completed



- Review of Solar Diffuser Stability Monitor (SDSM) gains indicated inadequate margin to saturation
  - Sun view observations through 2% screen showed potential saturation in worst case scenario
  - Instrument test successfully confirmed SDSM radiometric gains
- Sun view screen removed and replaced with lower transmitting screen
  - —Provided 15% to 20% margin against saturating the sun view
  - —Fix has been implemented on FM1 and PFM




## MODIS FM1 MW/LWIR Meets Radiometric Calibration Spec



Santa Barbara Remote Sensing

- Accuracy calculated from uncertainties in:
  - Center wavelength, BCS temperature, RVS, polynomial fit residuals
- May require RVS re-verification of Bands 29 and 30
  - On-going dialogue with GSFC/MCST

### Measured vs specified calibration accuracy






## MODIS FM1 RVS Is Not The Dominant Contributor



Santa Barbara Remote Sensing

- Contributors are assumed independent and RSS'd.
- Assumes On-Orbit Maneuver Quantifies Scan Mirror Emission.

### Accuracy as related to RVS






# On-Orbit Usage Requires Combining Calibration Accuracy With Noise



- Calibration accuracy spec written in terms of multiple samples
- Single sample accuracy must combine calibration accuracy (bias) and random noise (NEdL)






## **MODIS FM1 Calibration Accuracy Raytheon Converted to Temperature Domain**

Santa Barbara **Remote Sensing** 


### Calibration accuracy (K)





## MODIS FM1 Calibration Accuracy Combined With NEdT








## MODIS FM1 Reflectance Bands Radiance Accuracy



Santa Barbara Remote Sensing

- Specification spectral radiance accuracy 0.05
- Uncertainty includes: linear or quadratic fit residuals, SIS(100) radiance uncertainty; RVS @ 0.002 for VIS / NIR and 0.005 for SWIR
- Note that linear and quadratic fit residuals are very similar except for bands 1, 2, 17, & 18. Residuals are suggestive of SIS(100) linearity problems.

### **Reflectance region - Radiance uncertainty**






# MODIS FM1 Reflectance Bands Reflectance Accuracy



- Specification reflectance accuracy 0.02
- Uncertainty includes: linear or quadratic fit residuals, solar diffuser BRDF @ 0.016; RVS @ 0.002 for VIS / NIR and 0.005 for SWIR
- Note that linear and quadratic fit residuals are very similar except for bands 1, 2, 17, & 18. Residuals are suggestive of SIS(100) linearity problems.





## Summary/Issues



- FM1 demonstrates compliance to majority of calibration specifications
  - —Minor non-compliances flagged to GSFC
- Post TV FM1 ambient diagnostics completed
- FM1 ready for TV penalty test
- No changes expected in radiometric performance parameters
  - Both primary and redundant analog signal chains characterized with "A" processor; quiet configuration
- TV will verify fixes over environments
  - —Power supply shutdown
  - —Rdt noise anomaly





Santa Barbara Remote Sensing

## **Out-of-Band Spectral Data**

**Appendix**